

ICOLD committee F

Site C Clean Energy Project

Experience in planning (2007 to 2023)

June 11, 2023

Andrew Watson, P.Eng.

BC Hydro

Director Design Engineering – Site C


My background:

- **At BCHydro for about 22 years**
- **Background in geological/geotechnical engineering**
- **Leading the design work for BCHydro on site for 16 years. 8 of those years was before construction started**
- **Lead an integrated team of BCHydro engineers and consultants teams in the office and at the construction site.**
- **Report to the executive VP responsible for the project**
- **Coordinate the technical review boards for the project**

Outline:


- **Project overview and history**
- **Staged approach to evaluation and approval**
- **Project organization**
- **Scope of stages and decision points**
- **Formal environmental review**
 - **Alternates to the project**
 - **Alternates within the project**
- **Decision to proceed to construction**
- **Procurement, permits and oversight**
- **Construction Update**

Site C Clean Energy Project - Location




5-1



Peace River Flows



Peace River: Williston Reservoir, W.A.C. Bennett and Peace Canyon Dams



W.A.C. Bennett Dam



Peace Canyon Dam

Site C Clean Energy Project

DAM

- Type: Earthfill Dam
- Length: 1,050 metres
- Height: 60 metres
- Capacity: 1,100 MW
- Energy: 5,100 GWh/yr.

RESERVOIR

- Length: 83 km
- Width: 2-3 times current river (on average)

Transmission Lines

Substation


Auxiliary Spillway

Generating Station


Earthfill Dam

Spillway

Access Roads



A Mid-Sized Hydroelectric Facility



HISTORY OF SITE C

- **1958:** Site C first identified as potential third dam on Peace
- **1976:** Site C confirmed best option for third dam
- **1978-1982:** Historic Design Developed
- **1989-1991:** Design transfer to KCBL/SNC and Shelf Ready Plan
- **2004 and 2006:** BC Hydro long term plans recommend Site C as potential supply option
- **2007-2014:** Staged approach to planning, decisions and regulatory
- **2014:** Project approval and investment decision
- **2015-2023:** Construction
- (2017 had mid construction decision review)
- (2020 Budget update)



Building the Site C Clean Energy Project

Roads & highways

- Upgrades to 240, 269, 271 and Old Fort Roads
- Realignment of six segments of Highway 29

Anticipated timeline:

2015-2017 (upgrades); 2017-2021 (Highway 29 realignments)

Hudson's Hope shoreline protection

- Upgrades to DA Thomas Road
- Construction of a berm along the shoreline
- Re-paving of Clarke Ave, if required

Anticipated timeline:

2019-2021

Dam site area

- Site-preparation activities: clearing trees and vegetation, building access roads, constructing a temporary bridge, worker lodge and viewpoint and on-site excavations
- Construction activities: cofferdams and diversion tunnels, RCC buttress, earthfill dam, generating station, spillways and substation

Anticipated timeline:

2015-2016 (site preparation); 2016-2024 (project construction)

Peace River / Reservoir area

- Public safety signs and beacons installed upstream and downstream of the dam site
- Clearing activities, river diversion and reservoir filling

Anticipated timeline:

Late 2015 (public safety signs and beacons); 2015-2021 (clearing); 2019-2023 (river diversion); 2022-2024 (reservoir filling and operations)

Production & transport of materials

- Materials for Site C from Portage Mountain Quarry, West Pine Quarry and Wüthrich Quarry
- Transportation of materials by conveyor/truck from 85th Avenue to dam site

Anticipated timeline:


2015-2022 (production and transport of materials from quarries); 2017-2022 (transport of materials from 85th Avenue lands)

Transmission works

- Clearing activities along the 75 km transmission line corridor
- Construction of two new 500KV transmission lines
- Extension of Peace Canyon switchyard

Anticipated timeline:

2016-2017 (clearing); 2017-2022 (transmission line construction); 2017-2019 (Peace Canyon switchyard)



West Pine Quarry

MULTI-STAGE EVALUATION PROCESS



 Provincial government decision on whether to proceed to next stage

Engineering in the planning phase


- Conceptual and feasibility designs
- Alternates assessment
- Project design 'footprint' for environmental assessment and comparison of alternates
- Mitigation options and design
- Construction planning and constructability
- Procurement planning and interfaces
- Operations and maintenance (Safety by design)
- Environmental considerations
- Support the project consultations and environmental review

Environmental Assessment Support and Consultations, Refine project footprint

Engineering



Upon Award: Issue IFC Drawings; Provide Engineering Support to Fabrication and Construction



Project Footprint For Environmental Assessment
 Alternates to the project

TG Dimensions Input into MCW
 Final IFC Drawings for RCC Buttress

TG Dimensions Input into GSS
 Final IFC Drawings for GSS Tender Design

Confirmation of Procurement Packaging

Project requires an investment decision by the Province and regulatory permits and authorizations before it can proceed to construction

JULY 2015

MULTI-STAGE EVALUATION PROCESS




■ Provincial government decision on whether to proceed to next stage

Stage 2 Consultation and Technical review 2007 to 2009


Integrated Consultant / Owner Team

- Integrated consultant and owner team for all phases
- Commercially achieved by owner employees seconded to consultant team and consultants seconded to owner team
- Embed operations expertise in the design team at early stage
- Our goal is generally could not identify owner employees from consultants “Leave your business card at the door approach”



Stage 2: Consultation and Technical Review

- Commenced in the fall of 2007 and concluded in fall 2009.
- Consultations with the public, stakeholders, communities, Aboriginal groups and property owners, as well as early discussions with the Province of Alberta and the Northwest Territories.
- Conducted environmental and socio-economic baseline studies, and gathered engineering and technical information regarding the design, construction and operation of the project.
- Stage 2 Report, and 35 appended studies and reports, at: www.bchydro.com/sitec




PUBLIC AND STAKEHOLDER CONSULTATION

- BC Hydro-led Consultations
 - Public open houses
 - Stakeholder meetings
 - Local Governments
 - Property Owners
 - Business Liaison
- Regulatory Consultations
 - Multiple public comment periods
 - Public hearings, as part of Joint Review Panel Process
- Community Consultation Offices



Stage 3 Regulatory and Environmental Review 2010 to 2014

PROPOSED REGULATORY PROCESS



Environmental Assessment

Engineering Investigations



Forestry



Physical Environment



Wildlife



Fish and Aquatics



Heritage



Volume 1 Executive Summary, Introduction, Project Planning and Description	Volume 2 Assessment Methodology and Environmental Effects Assessment	Volume 3 Economic and Land and Resource Use Effects Assessment	Volume 4 Social, Heritage, and Health Effects Assessment	Volume 5 Asserted or Established Aboriginal Rights and Treaty Rights, Aboriginal Interests and Information, Environmental Management Plans, and Federal Information Requirements
1 Introduction	10 Effects Assessment Methodology	16 Local Govt Revenue	28 Population and Demographics	
2 Proponent Description	11 Environmental Background	17 Labour Market		4 Asserted or Established Aboriginal Rights and Treaty Rights, Aboriginal Interests and Information Requirements
3 Project Overview	11.1 Previous Developm 11.2 Geology, Terrain, ar 11.3 Land Status, Tenure Requirements 11.4 Surface Water Regi 11.5 Water Quality 11.6 Groundwater Regi 11.7 Thermal and Ice Re 11.8 Fluvial Geomorphology and Sediment Transport Regime 11.9 Methylmercury 11.10 Microclimate 11.11 Air Quality 11.12 Noise and Vibration 11.13 Electric and Magnetic Field			
4 Project Description		20 Agriculture	31 Transportation	35 Summary of Environmental Management Plans
5 Need for, Purpose of, and Alternatives to the Project		21 Forestry	32 Heritage Resources	36 Compliance Reporting
6 Alternative Means of Carrying out the Project	12 Fish and Fish Habitat	22 Oil, Gas and Energy	33 Human Health	37 Requirements for the Federal Environmental Assessment
7 Project Benefits	13 Vegetation and Ecological Communities	23 Minerals and Aggregates		38 Summary of Potential Residual Effects of the Project
8 Assessment Process	14 Wildlife Resources	24 Harvest of Fish and Wildlife Resources		39 Complete Lists of Mitigation and Follow-up Measures
9 Information Distribution and Consultation	15 Greenhouse Gases	25 Outdoor Recreation and Tourism		40 Conclusions
		26 Navigation		
		27 Visual Resources		


Need for, Purpose of and Alternates to the Project

WHY BUILD SITE C (Business Case)

- Site C adds 5,100 GWh/yr. of energy and up to 1,100 MW of capacity
- Ability to back up intermittent resources (e.g., wind, run-of-river hydro)
- Clean, reliable power for more than 100 years
- Low GHGs per megawatt hour
- Cost-effective option for ratepayers
- Fosters economic development



Looking ahead to 2025



*Includes BC Hydro heritage assets and contracted amounts with independent power producers (adjusted for attrition).

Low greenhouse gas emissions

CO₂e/kWh

Carbon dioxide equivalent per kilowatt hour; a term used for describing different green house gasses in a common unit.

10.5g

CO₂e/kWh



11g

CO₂e/kWh



48g

CO₂e/kWh



490g

CO₂e/kWh



820g


CO₂e/kWh



A dependable, 24/7 resource

Site C can quickly

↑ **increase or decrease** ↓
generation to match demand.




SITE C: COMPARING THE OPTIONS


- Lowest cost:
- Energy and capacity
- Fewer greenhouse gas emissions: Site C will have the lowest greenhouse gas emissions
- Economic development

Volume 1 Executive Summary, Introduction, Project Planning and Description	Volume 2 Assessment Methodology and Environmental Effects Assessment	Volume 3 Economic and Land and Resource Use Effects Assessment	Volume 4 Social, Heritage, and Health Effects Assessment	Volume 5 Asserted or Established Aboriginal Rights and Treaty Rights, Aboriginal Interests and Information, Environmental Management Plans, and Federal Information Requirements
1 Introduction	10 Effects Assessment Methodology	16 Local Govt Revenue	28 Population and Demographics	
2 Proponent Description	11 Environmental Background	17 Labour Market		4 Asserted or Established Aboriginal Rights and Treaty Rights, Aboriginal Interests and Information Requirements
3 Project Overview	11.1 Previous Developm 11.2 Geology, Terrain, ar 11.3 Land Status, Tenure Requirements 11.4 Surface Water Regi 11.5 Water Quality 11.6 Groundwater Regi 11.7 Thermal and Ice Re 11.8 Fluvial Geomorphology and Sediment Transport Regime 11.9 Methylmercury 11.10 Microclimate 11.11 Air Quality 11.12 Noise and Vibration 11.13 Electric and Magnetic Field			
4 Project Description		20 Agriculture	31 Transportation	35 Summary of Environmental Management Plans
5 Need for, Purpose of, and Alternatives to the Project		21 Forestry	32 Heritage Resources	36 Compliance Reporting
6 Alternative Means of Carrying out the Project	12 Fish and Fish Habitat	22 Oil, Gas and Energy	33 Human Health	37 Requirements for the Federal Environmental Assessment
7 Project Benefits	13 Vegetation and Ecological Communities	23 Minerals and Aggregates		38 Summary of Potential Residual Effects of the Project
8 Assessment Process	14 Wildlife Resources	24 Harvest of Fish and Wildlife Resources		39 Complete Lists of Mitigation and Follow-up Measures
9 Information Distribution and Consultation	15 Greenhouse Gases	25 Outdoor Recreation and Tourism		40 Conclusions
		26 Navigation		
		27 Visual Resources		


Alternate Means of Carrying out the Project




Highway 29 Realignment Options




Potential Highway Realignment – Lynx Creek Segment



Potential Highway Realignment – Farrell Creek Segment




Potential Highway Realignment – Halfway River Segment




Potential Highway Realignment – Bear Flat Segment

2 Dam Cascade – 7b + Low C3



Multi-Attribute Framework



Major Design alternates underwent multi-attribute analysis, for example:

- General arrangement
- Dam Type
- Spillway type, basin type, gate types
- Transmission corridor
- Number of units
- Arrangement of powerhouse
- Reservoir filling option

- Also used for foundation enhancements during construction


Example, for the selection of the generation arrangement involved:

- 1) A comparative Failure Modes and Effects Analysis (FMEA);
 - 2) A comparative Robustness and Functionality assessment;
 - 3) An Environmental and Socio-Economic impact evaluation;
- and
- 4) Cost and schedule and risk.

Various approaches used all similar themes:

Process used to both screen out alternates, conduct sensitivities analysis in terms of what could change the decision and ultimately develop a narrative documenting the decision.

Spillways




Spillway:

- 3 surface radial spillway gates, each 16.5 m wide by 12.7 m high;
- 6 low level vertical lift gates, each 6.5 m wide by 9.0 m high;
- 137 m long auxiliary free crest spillway;
- two-stage stilling basin separated by downstream weir;
- central dividing wall;
- jet deflectors for mitigation of total dissolved gas;
- 16,500 m³/s at the maximum reservoir surcharge



Spillway PMF discharge in General Model

Option selection: Orifice installation in Tunnel 2 for reservoir filling



ENVIRONMENTAL ASSESSMENT COMPLETE

- **7+ years** of consultation with First Nations, public and communities
- **14,000+** entries in First Nations consultation log
- **500+** consultation meetings with the public and stakeholders, property owners, and local governments
- **Multiple years** of field studies for fish, wildlife, socio-economic, environment
- **15,000+** pages in the Site C Environmental Impact Statement
- **70+** pages of mitigation, management and monitoring measures proposed
- **7,094** information requests responded to
- **Two-month** public hearing process (December 2013 to January 2014)
- **29,572** pages of evidence filed

PROJECT APPROVED

- Project received approval from the provincial government in December 2014.
- Approval followed extensive due diligence process that found Site C provides most affordable clean electricity, compared to alternatives.
- Construction planned to start in summer 2015.



Driver	Measurable Procurement Objectives
Cost/Value & Finance	<ul style="list-style-type: none"> • Deliver project within budget, maximize cost certainty • Optimize UEC
Schedule	<ul style="list-style-type: none"> • Minimize schedule interfaces; incentives to meet or exceed schedule milestones
Interfaces	<ul style="list-style-type: none"> • Does the packaging minimize the number and criticality of interfaces that BC Hydro has to manage?
Risk	<ul style="list-style-type: none"> • Allocate risk to party best able to manage that risk
Contractor Capability and Capacity	<ul style="list-style-type: none"> • Maximize interest from qualified proponents; minimum of three competitive bids to be received for each package from qualified proponents
First Nations and Regional Participation	<ul style="list-style-type: none"> • Meet project objectives and obligations
Governance	<ul style="list-style-type: none"> • Ensure fit between BC Hydro's competencies and the requirements of the contractors' role
Quality	<ul style="list-style-type: none"> • Maximize owner's responsibility for level of quality and oversight of QM

Interfaces and Contract packaging

The Site C project design includes the following key components:

DAM SITE COMPONENTS	OFF-SITE COMPONENTS	EARLY WORKS
<ul style="list-style-type: none"> • Earthworks • Generating Station and Spillways • Turbines and Generators 	<ul style="list-style-type: none"> • Clearing • Public Road Infrastructure • Transmission • Site C Substation 	<ul style="list-style-type: none"> • Early Clearing • Early Civil Works • Worker Accommodation and Site Services

Constructability and Operations and Maintenance

- Constructability review of designs
 - Part of design process
 - An element early procurement engagement
 - Alternate assessments
- Operations and maintenance review and input into design (environmental mgmt. included ops)
 - Documentation of owner requirements
 - Input into alternates
 - Safety by design (assess, confined spaces, etc)
 - Review of designs and checking design to owner requirements

Procurement Analysis and Support

- Technical and design input into contract packaging, contract type and procurement
- Design risks and technical risk to be transferred was important part of packaging, contract type and evaluation
- Design and construction interfaces
- Potential for design changes during construction

Engineering oversight and quality

- Design review boards, 4 member board
- Added an additional 2 member board mid-construction
- Independent specialist design reviews on a risk basis
- Owner review for maintenance and operability
- Quality planning
 - Engineering quality plan
 - Manufacturing
 - Construction (Quality Control and Quality Assurance and Site Engineering)

Construction Update

- **Construction started mid 2015**
- **River diversion fall 2020 during covid 19**
- **Reservoir filling schedule for fall 2023**



June 3, 2023



Approach Channel Flights


May 27, 2023



SCROLL OR PINCH TO ZOOM

Downstream Cofferdam





April 18, 2023

Highway 29 Realignment Cache Creek Bridge Concrete Complete





Setting up wildlife monitoring units



Frequent inspections by federal and provincial regulators



Working with Indigenous Groups

(Always) In the News: Typical Google News search results



First Nations challenge of Site C permits denied by BC Su...
CBC.ca - 4 hours ago

The province's highest court rejected a petition by two B.C. First Nations on Monday to overturn provincial permits issued for construction of the ...

BC Supreme Court rejects **Site C** permits challenge
Alaska Highway News - 3 hours ago

[View all](#)



Landowners fight Site C deadline from BC Hydro
CBC.ca - Oct 31, 2016

It is the final day for some landowners to sign a deal with BC Hydro to make way for construction of the **Site C** dam, but at least one couple is ...



Taxpayers on the hook for Site C dam until 2094
Alaska Highway News - 3 hours ago

Excavation crews dredge the Peace River near Old Fort in April as part of fish enhancement work just downstream of the **Site C** dam site.



B.C. Supreme Court rules against anti-Site C First Nations
MetroNews Canada - 15 hours ago

Construction continues on the **Site C** Clean Energy Project, pictured here in July, an estimated \$9-billion hydroelectric dam that BC Hydro says ...

BC Supreme Court dismisses challenge to provincial permits issued ...
CKNW News Talk 980 - 20 hours ago

[View all](#)



NWT Dene leaders call for halt to BC's Site C dam constr...
CBC.ca - Oct 25, 2016

Dene leaders in the N.W.T. are calling for an immediate halt on construction of the **Site C** Dam in northern B.C., saying it violates treaty rights on ...



BC Supreme Court throws out First Nations Site C challenge
MY PG NOW - 20 hours ago

The BC Supreme Court has thrown out a challenge by the Prophet River First Nation and West Moberly First Nations against the provincial ...



Site C worker lodge ready to house 1600 employees in F...
CBC.ca - Oct 19, 2016

Approximately a year after construction began, BC Hydro's **Site C** employee accommodation lodge is ready to house 1,600 workers in Fort St.

BC Hydro opens \$470m camp for **Site C** workers
Calgary Herald - Oct 20, 2016

[View all](#)



Vaughn Palmer: Bill Bennett says Site C is right thing, but ...
Vancouver Sun - Oct 30, 2016

"**Site C** is probably the most important thing that I was associated with in my 16 years," says the Kootenay East MLA and current minister of ...



Local businesses slow to benefit from Site C's growing ec...
Vancouver Sun - Oct 25, 2016

JOHN — Construction on B.C. Hydro's \$8.8-billion **Site C** dam project has ramped up to a 24/7 operation that is leaving an increasing, if uneven ...

Keeping the community informed

Bi-weekly bulletins



CONSTRUCTION BULLETIN

March 4, 2016

Site C Construction Schedule: March 7 – March 20

The following construction activities are scheduled to occur March 7 – March 20:

- Construction of the worker accommodation lodge and other buildings will continue. The first phase of the lodge (300 beds) will be open and in use.
- Clearing, excavation and road construction will continue on the north bank of the dam site area.
- Excavation and in-river roadwork will continue in and around the Peace River at the dam site.
- Construction of the temporary Peace River construction bridge will continue. Pile driving is being used to construct the bridge.
- Vegetation and tree clearing will occur in the area in and around the confluence of the Moberly River and along the Peace River.
- Clearing and other work will continue on the south bank. Road maintenance activities will continue on the south bank petroleum development roads.
- Security gates, guard buildings and mobile trailers will be installed.
- The main civil works contractor is expected to begin mobilization of crews and equipment to the dam site area. Survey work and site investigation will occur on the north and south bank.
- Operations will continue in Wuthrich Quarry.
- Vegetation and tree clearing will occur to accommodate future work in Portage Mountain Quarry.
- The Ministry of Transportation and Infrastructure's contractor may mobilize and begin work on public roads. Clearing will occur along 271 Road and Old Fort Road.
- Geotechnical investigations will occur along the right-of-way for the 500 kV transmission line.
- Geotechnical investigations may occur along Highway 29 at Cache Creek/Bear Flat.

Please note that all activities listed in this construction bulletin are based on the latest information in our construction plan and are subject to change.

What to Expect

While this work takes place, local residents can expect the following:

- There will be truck traffic in the area as construction crews mobilize, the hauling of rock and timber continues,



January 22, 2016



BC Hydro
Power smart

January 7



BC Hydro
Power smart

February 5, 2016

January 21

January 21:

continue, as modular dormitory units

of the dam site.

er at the dam site.

: Pile driving, including vibratory

ence of the Moberly River and

: River at the dam site.

tinue. Pile driving is being used to

influence of the Moberly River and

ance activities will continue on the

ws and equipment to the dam site area.

) kV transmission line.

Bear Flat.

n the latest information in our

e hauling of rock and timber continues,

ased industrial traffic on resource

ke place seven days per week, with

curring in Wuthrich Quarry.

s on the weekends. Some noise will

river work areas. These areas are

as modular dormitory units

in site.

dam site.

ing, including vibratory

he Moberly River and

as will continue on the

he south bank.

orth bank.

s on the north bank.

oment to the dam site area.

information in our

latest information in our

hauling of rock and timber

ased industrial traffic on


ven days per week, with

kends. Some noise will

led construction activities.

Possible Discussion topics:

- Post decision to proceed reviews
- Legal framework and challenges
- Other



For more information:
www.bchydro.com/sitec